APPENDIX II

SANITARY SEWER LATERAL
AND
SANITARY SEWER CONNECTION

Before you Dig - Pennsylvania Act 187, Underground Utility Line Protection Law of 1996
Requires You Call Pennsylvania One Call 1-800-242-1776

1. General – Sanitary sewer lateral shall include connection to the public sewer, sight tee, test tee, clean-outs, running trap with fresh air vent, a grease trap where required, and connection to the building drain. Down-spouts, rain conductors, driveway drains, area drains, or french drains shall not be connected to the sanitary sewer lateral.

2. Size - Residential - 4" minimum diameter pipe that is installed to a minimum slope of 1/4" per foot. Non-Residential - 6" minimum diameter pipe that is installed to a minimum slope of 1/8" per foot.

3. Materials – The sanitary sewer lateral shall be Schedule 40 solid core PVC, except in the case of 6" pipe that may be SDR 35 or Schedule 40 solid core PVC. A running trap the same size as the sanitary sewer lateral with a vent pipe and plastic mushroom vent cap shall be installed no less than two (2) and no more than five (5) feet from the outer face of the outside wall. The pipe as it exits the building wall shall be installed at a minimum depth of 48". Vent pipes and clean-outs are not permitted to be located in driveways, cartpaths, walkways or other finished surface areas unless prior approval is granted by the Authority. The vent cap shall be installed 6" above grade to prevent the inflow of water into the sanitary sewer lateral.

   Food preparation establishments and other establishments at the discretion of the Authority shall install grease traps of a style and size acceptable to the Authority. Sinks in food preparation areas of these establishments shall also have under-sink grease traps.

4. Clean-Outs and Directional Changes - Clean-outs, consisting of a wye branch fitting, a curved fitting, riser pipe and a watertight cap are required every 100 feet or at all directional changes greater than 45 degrees. No 90 degree bends shall be permitted. No exceptions.

5. Adapters - Approved adapters as manufactured by Fernco, Inc., or approved equivalent, may be used to connect pipe joints, reduce 6" pipe to 4" and connect the building drain to the running trap. All adapters shall be stainless steel shielded couplings with stainless steel clamps or must be encased in concrete.

6. Installation - Before digging the trench, the installer should expose the sanitary sewer connection and the building drain. Trench width shall be kept to a minimum width and have uniform slope as near as possible at right angles to the street. Excavate all trenches

at least 6" below the bottom of the pipe. Place an aggregate l gravel size (2B), in the trench to grade of the pipe. Install th dirt or water from entering the pipe. Place 12" of 2B stone ag ensuring uniform bedding to all sides of the pipe. The remai backfilled with material from the original excavation. Any par a traffic area must be filled to the level of the existing grade modified. The sanitary sewer lateral trench shall have a m separation and 18" vertical separation from other pipelines su gas lines, french drains or storm sewers. An Authority insp visually inspect the backfilling of the sanitary sewer lateral tren

7. Inspection - The Authority shall be notified at least 24 hours the building drain, sanitary sewer lateral and related appurtena be conducted prior to the connection to the trap, unless the buil sewer lateral are to be inspected at the same date, and prior to shall be capped prior to inspection. The inspection shall consis 5 minutes without any loss of pressure, or a hydrostatic test wh filled sanitary sewer lateral for 5 minutes, a visual inspec recording of pertinent information relating to the installation o not be scheduled until all Applications for Service have been su do not pass inspection, a fee will be levied and must be paid b sanitary sewer lateral will be scheduled.

8. Final Connection - If a completed connection to the building time of the installation of the sanitary sewer lateral, a tempo welded into the end of the lateral and shall not be remove connection is made to the building drain and an Authority Re visually inspect the final connection and backfilling of the trenc

9. Final Inspection - Prior to the issuance of an Occupancy Permi the Authority will conduct a final inspection of the property facilities located within the property have been installed and with Authority specifications. The Authority's inspector will Inspection Form to be forwarded to Rostraver Township for the the Occupancy Permit. Any deficiencies cited during the F corrected prior to the Authority's release of the Final Inspe Township.

10. Grinder Pumps - Grinder pumps for individual sewer service used only when gravity service is not available or is not recommended grinder pump for this type of service is the E/On Model DH071, as manufactured by Environment One Corpor accept all maintenance responsibilities for E/One grinder homeowner entering into a service agreement with the Authori pumps and their operation, maintenance (if not an E/One grin not the responsibility of the Authority, but that of the property o